

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED

NOTES:

- 1) THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH REQUIREMENTS OF THE 2006 IBC AND THE 2006 IRC WITH STATE OF TEXAS MODIFICATIONS AND WITH THE 2009 IBC, 2009 IRC, 2012 IBC, 2012 IRC, 2015 IBC AND 2015 IRC.
- 2) WOOD FRAMING TO BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO STRUCTURE. FRAMING IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
- 3) ALLOWABLE STRESS INCREASE OF 1/3 WAS NOT USED IN THE DESIGN OF THE PRODUCT SHOWN HEREIN. WIND LOAD DURATION FACTOR Cd=1.6 WAS USED FOR WOOD ANCHOR CALCULATIONS.
- 4) APPROVED IMPACT PROTECTIVE SYSTEM IS NOT REQUIRED FOR THIS PRODUCT IN WIND BORNE DEBRIS REGIONS UP TO WIND ZONE 3.
- 5) DESIGN PRESSURE AND INSTALLATION DETAILS SHOWN IN THIS DOCUMENT APPLY ONLY TO MULLION. WINDOWS MUST BE APPROVED UNDER SEPARATE APPROVAL.
- 6) SINGLE WINDOWS TO BE MULLED ARE NOT LIMITED TO THOSE SHOWN IN THIS DRAWING. WINDOWS MUST BE MANUFACTURED BY MI WINDOWS AND DOORS, INC.
- 7) DESIGN PRESSURE OF MULLED UNIT SHALL BE CONTROLLED BY THE LESSER DESIGN PRESSURE OF THE MULLION OR THE INDIVIDUAL WINDOW OR DOOR UNIT.
- 8) UNITS MAY BE MULLED TOGETHER INDEFINITELY AS LONG AS SINGLE UNIT WIDTH AND HEIGHT ARE NOT EXCEEDED AND MULLION IS ANCHORED AS SHOWN HEREIN.
- 9) MULLION VERTICAL INSTALLATION IS SHOWN, MULLION MAY BE USED IN HORIZONTAL APPLICATIONS AS LONG AS DIMENSIONS INDICATED HEREIN ARE NOT EXCEEDED AND MULLION IS ANCHORED ACCORDING TO THIS DOCUMENT.

DESIGN PRESSURE TABLE INSTRUCTIONS:

- 1) DEFINE REQUIRED DESIGN LOAD PER TEXAS BUILDING CODE CHAPTER 16.
- 2) DETERMINE TRIBUTARY WIDTH AND MULLION SPAN BASED ON PRODUCT TO BE INSTALLED. SEE FORMULA FOR TRIBUTARY WIDTH.
- 3) LOCATE MULLION SPAN (UNIT HEIGHT) AND TRIBUTARY WIDTH. AT THE INTERSECTION OF ROW AND COLUMN CONTAINING THE MULLION SPAN AND TRIBUTARY WIDTH RESPECTIVELY IS THE MULLION RATING FOR PRODUCT IN STEP 2.  
MULLION RATING MUST BE EQUAL OR GREATER THAN REQUIRED DESIGN PRESSURE OBTAINED IN STEP 1.

$$\text{TRIBUTARY WIDTH} = \frac{W1 + W2}{2}$$

ANCHORING NOTES:

- 1) FOR ANCHORING INTO WOOD FRAMING OR 2X BUCK USE #10 WOOD SCREW WITH SUFFICIENT LENGTH TO ACHIEVE A 1 3/8" MINIMUM EMBEDMENT. LOCATE ANCHORS AS SHOWN IN INSTALLATION DETAILS SHEET 3.
- 2) FOR ANCHORING INTO CONCRETE USE 1/4" ELCO ULTRACON TAPCON WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT WITH 1" MINIMUM EDGE DISTANCE. LOCATE ANCHORS AS SHOWN IN INSTALLATION DETAILS SHEET 4.
- 3) FOR ANCHORING INTO METAL FRAMING USE #10 SMS OR SELF DRILLING SCREW WITH SUFFICIENT LENGTH TO ACHIEVE A 3 THREADS MINIMUM BEYOND STRUCTURE INTERIOR WALL. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
- 3) FOR ATTACHING WINDOW UNITS TO MULLION USE #10 SELF DRILLING SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE A MINIMUM EMBEDMENT OF THREE THREADS PAST THE MULLION WALL. LOCATE SCREWS IN ACCORDANCE WITH WINDOW ANCHORING SCHEDULE AS SHOWN IN WINDOW SEPARATE APPROVAL
- 4) ALL FASTENERS TO BE CORROSION RESISTANT.
- 5) INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BELOW:
  - A. WOOD – MINIMUM SPECIFIC GRAVITY OF G=0.42
  - B. CONCRETE – MINIMUM COMPRESSIVE STRENGTH OF 3,200 PSI.
  - C. MASONRY – STRENGTH CONFORMANCE TO ASTM C-90, GRADE N, TYPE 1 (OR GREATER).
  - D. METAL STRUCTURE – STEEL 18GA (.048") FY=33KSI/FU=52KSI OR ALUMINUM 6063-T5 FU=30KSI .062" THICK MINIMUM

TABLE OF CONTENTS	
SHEET NO.	DESCRIPTION
1	NOTES
2	CONFIGURATIONS AND DP CHART
3	INSTALLATION DETAILS
4	COMPONENTS



<b>MI WINDOWS AND DOORS, LLC</b> 650 WEST MARKET STREET GRATZ, PA 17030-0370		
5765 VERTICAL MULLION 83" MULLION SPAN GENERAL NOTES		
DRAWN: A.R.	DWG NO. 08-03427	REV -
SCALE NTS	DATE 04/16/19	SHEET 1 OF 4
L. ROBERTO LOMAS P.E. 1432 WOODFORD RD LEWISVILLE, NC 27023 434-688-0609 rllomas@rlomaspe.com		

SIGNED: 05/02/2019



Luis R. Lomas P.E.  
TX No.: 101889

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED



**APPROVED CONFIGURATIONS**  
 MULTIPLE UNITS MAYBE MULLED TOGETHER AS LONG AS COMBINED WIDTH DOES NOT EXCEED 107 3/8" AS SHOWN HEREIN.

**Design pressure rating (psf)**  
 For units installed in wood and metal framing

Mullion span (in)	Tributary width (in)					
	18.13	25.50	36.00	42.00	48.00	52.13
25.00	120.0	120.0	120.0	120.0	120.0	120.0
37.38	120.0	120.0	120.0	120.0	120.0	120.0
49.63	120.0	120.0	120.0	120.0	120.0	120.0
62.00	120.0	120.0	116.7	107.4	101.4	98.7
65.63	120.0	120.0	107.8	98.7	92.5	89.7
72.00	120.0	120.0	95.1	86.3	80.3	77.2
84.00	120.0	87.0	64.0	56.4	51.0	48.1

LARGE AND SMALL MISSILE IMPACT, LEVEL D, WIND ZONE 3  
 DIMENSIONS IN CHART ARE FRAME DIMENSIONS AND DO NOT INCLUDE FLANGE

**Design pressure rating (psf)**  
 For units installed in masonry/concrete

Mullion span (in)	Tributary width (in)					
	18.13	25.50	36.00	42.00	48.00	52.13
25.00	120.0	120.0	120.0	120.0	120.0	120.0
37.38	120.0	120.0	120.0	120.0	120.0	120.0
49.63	120.0	120.0	113.8	107.8	105.4	105.3
62.00	120.0	103.2	81.8	75.3	71.1	69.2
65.63	120.0	96.1	75.6	69.1	64.9	62.8
72.00	113.6	85.8	66.7	60.5	56.3	54.1
84.00	95.4	71.3	54.5	49.0	45.0	42.9

LARGE AND SMALL MISSILE IMPACT, LEVEL D, WIND ZONE 3  
 DIMENSIONS IN CHART ARE FRAME DIMENSIONS AND DO NOT INCLUDE FLANGE

**MI WINDOWS AND DOORS, LLC**  
 650 WEST MARKET STREET  
 GRATZ, PA 17030-0370

5765 VERTICAL MULLION  
 83" MULLION SPAN  
 APPROVED CONFIGURATIONS AND RATING CHARTS

DRAWN: A.R.	DWG NO. 08-03427	REV -
SCALE NTS	DATE 04/16/19	SHEET 2 OF 4


L. ROBERTO LOMAS P.E.  
 1432 WOODFORD RD LEWISVILLE, NC 27023  
 434-688-0609 rllomas@rlomaspe.com

SIGNED: 05/02/2019




Luis R. Lomas P.E.  
 TX No.: 101889

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED




**VERTICAL CROSS SECTION**  
**MASONRY/CONCRETE AND WOOD FRAMING**  
**INSTALLATION**

- NOTES:
- 1) FOR FRAMING INSTALLATION USE ALL FOUR HOLES IN INSTALLATION CLIP.
  - 2) FOR MASONRY/CONCRETE INSTALLATION USE HOLES AT EACH END OF INSTALLATION CLIP. INSTALL TWO TAPCONS PER CLIP.



**CLIP INSTALLATION**



**VERTICAL CROSS SECTION**  
**METAL INSTALLATION**

MI WINDOWS AND DOORS, LLC  
 650 WEST MARKET STREET  
 GRATZ, PA 17030-0370

5765 VERTICAL MULLION  
 83" MULLION SPAN  
 INSTALLATION DETAILS

DRAWN: A.R.	DWG NO. 08-03427	REV -
SCALE NTS	DATE 04/16/19	SHEET 3 OF 4


L. ROBERTO LOMAS P.E.  
 1432 WOODFORD RD LEWISVILLE, NC 27023  
 434-688-0609 rllomas@rlomaspe.com

SIGNED: 05/02/2019





Luis R. Lomas P.E.  
 TX No.: 101889

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED



**SECT5765 MULLION**  
ALUMINUM 6005-T5 .125" THICK



**SECT5768 CLIP**  
ALUMINUM 6063-T5 .093" THICK

SIGNED: 05/02/2019

MI WINDOWS AND DOORS, LLC  
650 WEST MARKET STREET  
GRATZ, PA 17030-0370

5765 VERTICAL MULLION  
83" MULLION SPAN  
COMPONENTS

DRAWN: A.R.	DWG NO. 08-03427	REV -
SCALE NTS	DATE 04/16/19	SHEET 4 OF 4

L. ROBERTO LOMAS P.E.  
1432 WOODFORD RD LEWISVILLE, NC 27023  
434-688-0609 rllomas@rlomaspe.com



Luis R. Lomas P.E.  
TX No.: 101889