

STRUCTURAL NOTES:

- THIS SYSTEM HAS BEEN DESIGNED AND TESTED IN ACCORDANCE WITH THE 2018 INTERNATIONAL BUILDING/RESIDENTIAL CODE. THIS SYSTEM SHALL NOT BE INSTALLED IN ESSENTIAL FACILITIES. TEST STANDARDS USED – ASTM E330, ASTM E1886 AND ASTM E1996. THE ADEQUACY FOR IMPACT, DEFLECTION AND FATIGUE RESISTANCE HAS BEEN VERIFIED IN ACCORDANCE WITH THE ABOVE REFERENCED CODE, AND AS PER THE 2018 INTERNATIONAL BUILDING/RESIDENTIAL CODE; TAS 201, 202 AND 203 AT FENESTRATION TESTING LABORATORY, INC. PER THEIR REPORT(S) LISTED HEREIN.
- DESIGN PRESSURE REQUIREMENTS OF A SPECIFIC SITE SHALL BE DETERMINED BY OTHERS IN CONFORMANCE TO THE 2018 INTERNATIONAL BUILDING/RESIDENTIAL CODE AS REQUIRED BY THE JURISDICTION WHERE THE SYSTEM WILL BE INSTALLED. WHEN CALCULATING PRESSURES PER ASCE 7-16, USE OF DIRECTIONALITY FACTOR  $K_d=0.85$  IS ALLOWED.
- NO 33-1/3% INCREASE IN ALLOWABLE STRESS INCREASE HAS BEEN USED IN THE DESIGN OF THIS PRODUCT.
- THIS PRODUCT EVALUATION DOCUMENT (PED) DETAILED HEREIN IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SPECIFIC SITE. IF SITE CONDITIONS DEVIATE FROM THE CONDITIONS DETAILED HEREIN, A LICENSED ENGINEER OR REGISTERED ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS TO BE USED IN CONJUNCTION WITH THIS DOCUMENT.
- THE CONTRACTOR AND / OR PERMIT HOLDER IS TO BE RESPONSIBLE FOR THE SELECTION, PURCHASE AND INSTALLATION OF THIS SYSTEM, INCLUDING VERIFYING THE ADEQUACY OF THE EXISTING STRUCTURE TO WITHSTAND THE NEW SUPERIMPOSED LOADS SHOWN BELOW AND THE SOUNDNESS OF THE STRUCTURE WHERE THE SYSTEM IS TO BE ATTACHED TO INSURE PROPER ANCHORAGE.
- SITE SPECIFIC PROJECTS SHALL BE PREPARED BY A TEXAS LICENSED ENGINEER OR ARCHITECT WHO WILL BECOME THE ENGINEER OF RECORD (EOR) FOR THE PROJECT AND WHO WILL BE RESPONSIBLE FOR THE PROPER USE OF THE PED ENGINEER OF RECORD, ACTING AS A DELEGATED ENGINEER TO THE PED ENGINEER SHALL SUBMIT TO THIS ENGINEER THE SITE SPECIFIC DRAWINGS FOR REVIEW.
- THIS PED SHALL BEAR THE DATE AND ORIGINAL SEAL OF THE PROFESSIONAL ENGINEER OF RECORD THAT PREPARED IT.
- THIS SYSTEM MAY ALSO BE INSTALLED HORIZONTALLY FOLLOWING INSTALLATION DETAILS SHOWN HEREIN.
- THIS WIND ABATEMENT SYSTEM IS INTENDED FOR USE ONLY DURING HURRICANE OR OTHER TROPICAL STORM WARNINGS. SEASONAL OR PERMANENT INSTALLATION OR STORAGE OF THIS WIND ABATEMENT SYSTEM IN AREAS OF PROLONGED EXPOSURE TO DIRECT SUNLIGHT OR OTHER WEATHERING CONDITIONS MAY CAUSE MATERIAL DETERIORATION OR OTHERWISE INHIBIT THEIR ADEQUACY AS AN IMPACT RESISTANT SYSTEM.
- LIMITATIONS OF USE  
THIS NON POROUS SYSTEM HAS NO MINIMUM SEPARATION FROM GLAZING REQUIREMENT.  
THE MAXIMUM SIZE SHALL BE 60 PSF MAX. PRESSURE @ 216 INCHES MAXIMUM SPAN. SEE TABLE ON SHEET 1/2.
- RESERVED.
- ALL SCREWS TO BE STAINLESS STEEL 304 OR 316 SERIES OR CORROSION RESISTANT COATED CARBON STEEL WITH A 50 KSI YIELD STRENGTH AND A 90 KSI TENSILE STRENGTH.
- ALL BOLTS TO BE ASTM A307, GALVANIZED OR 304 SERIES STAINLESS STEEL WITH A MINIMUM 36 KSI YIELD STRENGTH.
- ANCHORS TO STRUCTURE (WALL / FLOOR / CEILING / SYSTEM) SHALL BE INSTALLED PER MANUFACTURERS' RECOMMENDATIONS AND AS FOLLOWS:
  - CONCRETE BLOCK MASONRY (ASTM C-90)  
TAPCON ANCHORS (ITW BUILDDEX) OR PANELMATE MALE & FEMALE FASTENERS (ELCO TEXTRON) – 1/4 IN. DIA.  
I. MINIMUM EMBEDMENT INTO HOLLOW CONCRETE BLOCK MASONRY FOR TAPCON ANCHORS AND ELCO PANELMATES IS 1 1/4 IN., FILLED MASONRY EMBEDMENT IS 1 3/4". NO EMBEDMENT INTO STUCCO SHALL BE PERMITTED.  
II. PAVERS, BRICKS OR OTHER PRE-CAST PRODUCTS LOCATED ON THE EXISTING STRUCTURE WALL OR FLOOR SHALL HAVE ANCHORS OF SUFFICIENT LENGTH TO PROPERLY ATTACH TO THE PRIMARY STRUCTURE BEHIND IT.  
III. MINIMUM EDGE DISTANCE = 3.0"
  - POURED CONCRETE ( $f'_c=3000$  PSI MIN.)  
TAPCON ANCHORS (ITW BUILDDEX) OR PANELMATE MALE & FEMALE FASTENERS (ELCO TEXTRON) – 1/4 IN. DIA.  
I. MINIMUM EMBEDMENT INTO POURED CONCRETE FOR TAPCON ANCHORS AND ELCO PANELMATES IS 1 3/4 IN. NO EMBEDMENT INTO STUCCO SHALL BE PERMITTED. SCREWS TO BE 1/4"-20 X 1 3/4" FOR STUCCO, 1 1/4" WITH NO STUCCO.  
II. PAVERS, BRICKS OR OTHER PRE-CAST PRODUCTS LOCATED ON THE EXISTING STRUCTURE WALL OR FLOOR SHALL HAVE ANCHORS OF SUFFICIENT LENGTH TO PROPERLY ATTACH TO THE PRIMARY STRUCTURE BEHIND IT.  
III. MINIMUM EDGE DISTANCE = 3.0"
  - WOOD (Nominal 2x4(min) "Southern Pine" SG=0.55 OR GREATER)  
TAPCON ANCHORS (ITW BUILDDEX) DIA. OR PANELMATE MALE & FEMALE FASTENERS (ELCO TEXTRON) – 1/4 IN.  
I. MINIMUM EDGE DISTANCE = CENTER OF 2" NOMINAL LUMBER (APPROX. 3/4"). MINIMUM EMBEDMENT = 1-1/2"
- MAXIMUM DESIGN PRESSURE VERSUS PANEL SPAN SHOWN ON SHEET 1/2
- SCREEN PANEL'S MANUFACTURER LABEL SHALL BE PLACED ON A READILY AND VISIBLE LOCATION ON THE PANEL. ONE LABEL SHALL BE PLACED FOR EVERY OPENING. LABEL SHALL READ AS FOLLOWS:  
HURRICANE FABRIC.COM LLC  
PO BOX 50153; CLAYTON, MO 63105  
TEXAS DEPARTMENT OF INSURANCE NUMBER: SHU-XXX. OPENING NO.: XX
- THIS DOCUMENT IN ITS ENTIRETY WILL BE CONSIDERED INVALID IF IT IS ALTERED BY ANY MEANS.

RETENTION CLIP END CONNECTOR:

RHODIA ENGINEERING PLASTICS – POLYAMIDE 66

FABRIC SPECIFICATION:


FIBER CONTENT: TEXTILE FABRIC  
CONSTRUCTION: 20 X 20 WEAVE  
FINISH: RESIN COATED  
WEIGHT (ASTM D-3776): 9.0 –OZ/SQUARE YARD  
TENSILE STRENGTH (GRAB METHOD, ASTM D -4632): WARP – 570 lbs., WEFT – 570 lbs.  
BURST STRENGTH (ASTM D – 3786): 1,000 PSI  
ABRASION RESISTANCE (ASTM D -4886) 95% STRENGTH RETAINED

SEWING:

ONLY SEWING IS AT SPLICE

EDGES:

NO SEWING AT EDGES



SPLICE DETAIL

FASTENER SPACING OF A SINGLE UNIT SCREEN FOR ANY LENGTH ATTACHED WITH 1/4" ELCO PANELMATE PRO, MALE & FEMALE (INCHES)

SCREEN SPAN	FILLED CMU (1900 PSI)				CONCRETE (4000 PSI)				HOLLOW CMU				TIMBER			
	PRESSURE (PSF)				PRESSURE (PSF)				PRESSURE (PSF)				PRESSURE (PSF)			
	60	50	40	30	60	50	40	30	60	50	40	30	60	50	40	30
4'-0"	15	18	18	18	17	18	18	18	11	13	15	18	10	11	13	16
6'-0"	11	12	15	18	12	14	16	18	8	9	10	13	7	8	9	12
8'-0"	7	8	10	12	8	9	11	13	5	6	7	9	5	5	6	8
10'-0"	6	7	8	10	7	8	9	11	4	5	6	7	-	4	5	6
12'-0"	5	6	7	9	6	7	8	9	-	4	5	6	-	-	4	6
14'-0"	4	5	6	7	5	5	6	8	-	-	4	5	-	-	-	5
16'-0"	-	5	5	6	4	5	6	7	-	-	-	5	-	-	-	4
18'-0"	-	-	5	6	-	4	5	6	-	-	-	4	-	-	-	-

FASTENER SPACING OF A SINGLE UNIT SCREEN FOR ANY LENGTH ATTACHED WITH 3/8" DROP-IN ANCHOR WITH SIDEWALK BOLT (INCHES)

SCREEN SPAN	FILLED CMU (1900 PSI)				CONCRETE (4000 PSI)				HOLLOW CMU				TIMBER			
	PRESSURE (PSF)				PRESSURE (PSF)				PRESSURE (PSF)				PRESSURE (PSF)			
	60	50	40	30	60	50	40	30	60	50	40	30	60	50	40	30
4'-0"	18	18	18	18	18	18	18	18	18	18	18	18	13	15	18	18
6'-0"	18	18	18	18	18	18	18	18	18	18	18	18	9	11	13	16
8'-0"	14	16	18	18	16	18	18	18	12	14	17	18	6	7	8	10
10'-0"	12	14	16	18	13	15	18	18	10	12	14	17	5	6	7	9
12'-0"	10	12	14	17	12	13	15	18	9	10	12	15	5	5	6	8
14'-0"	9	10	12	14	10	11	13	16	8	9	10	12	-	4	5	6
16'-0"	8	9	10	13	8	10	11	14	7	8	9	11	-	-	4	6
18'-0"	7	8	9	11	8	9	10	12	6	7	8	10	-	-	4	5

EVALUATION BASED ON:  
FENESTRATION TESTING LABORATORY, INC

LAB NO.: 6418 DATED 12/7/2010

ASTM E330-02 – UNIFORM STATIC LOADS  
ASTM E1886-05 & ASTM E1996-05 – LARGE MISSILE TYPE  
"D" IMPACT RESISTANCE & CYCLIC LOADING PERFORMANCE

LAB NO.: 5804 DATED 01/13/2009

TAS 202 – UNIFORM STATIC LOADS  
TAS 201, TAS 202 – LARGE MISSILE IMPACT RESISTANCE & CYCLIC LOADING PERFORMANCE

LIST OF REPORTS

John H. Kampmann Jr., PE  
TX License #: 108168  
DATE:

TEXAS DEPARTMENT OF INSURANCE

ASTRO GUARD  
Wind Abatement System

HURRICANE FABRIC.COM LLC  
1 FIRST MISSOURI CENTER  
ST. LOUIS, MO 63141  
PHONE: (561) 742-3756  
WWW.HURRICANEFABRIC.COM

DESCRIPTION  
XX/XX/XX-RESERVED


REV  
1

TX REG. #: F-13337  
WWW.MEAENGINEERS.COM

MEAE  
ENGINEERS, INC.  
5656 Lawton Drive  
Sarasota, Florida 34233  
(941) 922-3854 CA-6072


Drawn: JK  
Project #: 21-0915  
Scale: NTS  
Date: 2/22/21  
Sheet No.:

1/2




**TYPICAL TWO-SIDED INSTALLATION**  
VERTICAL OR HORIZONTAL INSTALLATION - N.T.S.


NOTE:  
PANELS CAN BE ATTACHED ON THREE OR FOUR SIDES.  
FOR FOUR SIDE ATTACHMENT THE SPAN IS IN THE SHORT  
DIMENSION BETWEEN FASTENERS



**BOTTOM MOUNTING CLIP DETAILS**  
INSIDE OR OUTSIDE MOUNT INSTALLATION - N.T.S.  
AVERAGE THICKNESS = 0.100 IN.  
MATERIAL SPECIFICATION = POLYAMIDE 66



**SECTION A-A (OPTION 1)**  
INSIDE MOUNT INSTALLATION - N.T.S.




**SECTION A-A (OPTION 2)**  
OUTSIDE MOUNT INSTALLATION - N.T.S.

**LOADS ON EXISTING STRUCTURE FROM SCREEN SYSTEM**  
TX = PARALLEL LOADS (PLF)


SPAN (INCHES)	PRESSURE (PSF)						
	60	55	50	45	40	35	30
216	1134	1070	1004	936	866	792	714
192	1020	962	903	842	778	712	642
168	905	854	801	747	690	631	570
144	744	702	659	614	568	519	469
120	651	615	577	538	497	455	410
96	553	521	489	456	422	386	348
72	353	333	312	291	269	246	222
48	254	240	225	210	194	178	160

**LOADS ON EXISTING STRUCTURE FROM SCREEN SYSTEM**  
TY = PERPENDICULAR LOADS (PLF)

SPAN (INCHES)	PRESSURE (PSF)						
	60	55	50	45	40	35	30
216	540	495	450	405	360	315	270
192	480	440	400	360	320	280	240
168	420	385	350	315	280	245	210
144	360	330	300	270	240	210	180
120	300	275	250	225	200	175	150
96	240	220	200	180	160	140	120
72	180	165	150	135	120	105	90
48	120	110	100	90	80	70	60



**TOP MOUNTING CLIP DETAILS**  
INSIDE OR OUTSIDE MOUNT INSTALLATION - N.T.S.  
AVERAGE THICKNESS = 0.100 IN.  
MATERIAL SPECIFICATION = POLYAMIDE 66



TEXAS DEPARTMENT OF INSURANCE

ASTRO GUARD  
Wind Abatement System

Drawn: JK  
Project #: 21-0915  
Scale: NTS  
Date: 2/22/21  
Sheet No.:

John H. Kampmann Jr., PE  
TX License #: 108168  
DATE:

TX REG. #: F-13337  
WWW.MEAENGINEERS.COM

**MEA**  
ENGINEERS, INC.  
5656 Lawton Drive  
Sarasota, Florida 34233  
(941) 922-3854 CA-6072

DESCRIPTION  
XX/XX/XX - RESERVED

HURRICANE FABRIC.COM LLC  
1 FIRST MISSOURI CENTER  
ST. LOUIS, MO 63141  
PHONE: (561) 742-3756  
WWW.HURRICANEFABRIC.COM